

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-21115-00-00  
Spot: NWSE Sec/Twnshp/Rge: 3-35S-12W  
2363 feet from S Section Line, 2404 feet from E Section Line  
Lease Name: LOHMANN Well #: 6-A  
County: BARBER Total Vertical Depth: 4868 feet

Operator License No.: 3273  
Op Name: HERMAN L. LOEB, LLC  
Address: PO BOX 838  
LAWRENCEVILLE, IL 62439

| String | Size  | Depth (ft) | Pulled (ft) | Comments        |
|--------|-------|------------|-------------|-----------------|
| PROD   | 4.5   | 4867       | 0           | WITH 126 SX CMT |
| SURF   | 8.625 | 325        |             | WITH 250 SX CMT |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/27/2015 8:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: ALAN VRATIL Company: HERMAN L. LOEB LLC Phone: (620) 886-2419

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE  
Date/Time Plugging Completed: 10/27/2015 5:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SPOT 25 SX COMMON CEMENT THROUGH TBG AT 4800'. SPOT 25 SX COMMON CEMENT AT 1500'. LET CMT SET. TAG TOC @ 1355'. PERFORATE 4 1/2" CASING AT 600'. RUN TBG TO 600'. PUMPED DOWN TBG WITH 250 SX CMT. CIRCULATED CMT TO SURFACE FILLING 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS FROM 600' TO SURFACE WITH CMT. LAID TBG DOWN. TOP OFF WELL & WELL CELLAR WITH 100 SX CMT.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4816 | 4826 |      |          |

Remarks: USED COMMON CMT & 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

*Stephen J. Pfeifer*  
SA  
(TECHNICIAN)

RECEIVED  
OCT 30 2015  
KCC DODGE CITY

KCC WICHITA  
NOV 12 2015  
RECEIVED

Form CP-2/3