

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-063-21198-00-00  
Spot: SESWSE Sec/Twnshp/Rge: 8-11S-31W  
330 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: WIELAND A Well #: 1  
County: GOVE Total Vertical Depth: 4719 feet

Operator License No.: 3273  
Op Name: HERMAN L. LOEB, LLC  
Address: PO BOX 838  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4719		200 SX
SURF	8.625	210		145 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/15/2015 9:30 AM  
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.  
Proposal Rcvd. from: TRACY HOLLIS Company: CHEYENNE WELL SERVICE, INC. Phone: (719) 340-8985

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Port Collar at 2518' w/350 sx cement.  
Packer stuck at 4000'. Shot tubing off at 3950'  
Perforations: 4204' - 4208', 4259' - 4263', 4610' - 4620'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/15/2015 9:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3945' and pumped 20 sx neat cement followed by 55 sx cement w/200 # hulls.  
Pulled tubing to 2997' and pumped 75 sx cement w/150 # hulls. Pulled tubing to 2112' and  
pumped 75 sx cement w/150 # hulls. Pulled tubing to 1200' and pumped 140 sx cement. Good  
circulation of cement. Pulled tubing out and topped off casing w/10 sx cement. Cement still  
falling. Let cement set till 10/19/2015.  
10/19/2015- Topped off casing with 49 sx redi mix cement. Tied on to backside and squeezed  
with 0 sx cement at 400 psi.

GPS: 39.10588 -100.78154

Perfs:


Top	Bot	Thru	Comments
4610	4620		
4259	4263		
4204	4208		

Remarks: ALLIED CEMENT TICKET # 76736

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

OCT 28 2015

KCC WICHITA

Form CP-2/3

NOV 16 2015

RECEIVED