

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-023-21446-00-00
Spot: SESWNWSE Sec/Twnshp/Rge: 7-2S-37W
1453 feet from S Section Line, 2135 feet from E Section Line
Lease Name: CASEY Well #: 2-7
County: CHEYENNE Total Vertical Depth: 4832 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	354		300 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/24/2015 12:00 AM
Plug Co. License No.: 6039 Plug Co. Name: L. D. DRILLING, INC.
Proposal Rcvd. from: RICK Company: L. D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 240 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS Witness Type: NONE
Date/Time Plugging Completed: 10/24/2015 8:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

1st plug @3230 w/50 sx
2nd plug @2439 w/100 sx
3rd plug @400 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx


Perfs:

Remarks: BASIC

Plugged through: DP

District: 04

Signed _____


(TECHNICIAN)

CM

OCT 29 2015

KCC WICHITA

Form CP-2/3

NOV 16 2015

RECEIVED