

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-153-20888-00-01
Spot: NESWSESW Sec/Twnshp/Rge: 30-5S-36W
431 feet from S Section Line, 3504 feet from E Section Line
Lease Name: BRINEY TRUST OWWO Well #: 1-30
County: RAWLINS Total Vertical Depth: 4842 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4830		260 SX
SURF	8.625	432		270 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/01/2015 1:30 PM
Plug Co. License No.: 34787 Plug Co. Name: GREEN OIL FIELD SERVICES, LLC
Proposal Rcvd. from: MIKE KASSELMAN Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 450 sx 60.40 pozmix 4% gel cement w/600 # gel and 500 # hulls.
8 5/8" surface casing set at 432' w/270 sx cement.
4 1/2" production casing set at 4830' w/260 sx cement.
TD 4842', PBSD 4803'.
Perforations: 4680' - 4685'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/01/2015 5:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing at 3132' and 2302'. Ran tubing to 4657' and pumped 600 # gel followed by 65 sx cement w/250 # hulls. Pulled tubing to 3125' and pumped 105 sx cement w/150 # hulls. Pulled tubing to 1595' and pumped 100 sx cement w/100 # hulls. Cement circulated to surface. Pulled tubing to surface. Connected to 4 1/2" casing and pumped 30 sx cement. Casing full. Connected to 8 5/8" surface casing and pumped 80 sx cement.

GPS: 39.58408 -101.40729

Perfs:

Top	Bot	Thru	Comments
4680	4685		

Remarks: GLOBAL OILFIELD SERVICES TICKET # 2542

Plugged through: TBG

District: 04

Signed Darrel Dipman

(TECHNICIAN)

CM

OCT 01 2015

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

NOV 06 2015

CONSERVATION DIVISION
WICHITA, KS