

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-21262-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 35-28S-11W
2310 feet from N Section Line, 2310 feet from E Section Line
Lease Name: BORTZ Well #: 1
County: PRATT Total Vertical Depth: 2700 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LAR
Address: 562 W STATE RD 4
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2698	1720	WITH 150 SX CMT
SURF	8.625	430		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/27/2015 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 25 SX CMT WITH 150# HULLS. PLUG AT 1720' WITH 10 SX GEL & 50 SX CMT. PLUG AT 480' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 10/27/2015 3:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 25 SX CMT & 150# HULLS TO 2500'. MAXIMUM PRESSURE 700#. SHUT IN PRESSURE 700#. 1ST PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 480' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2628	2642		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.
Plugged through: CSG

District: 01

Signed E. McIntyre
(TECHNICIAN)

RECEIVED
NOV - 4 2015
KCC DODGE CITY

JA

KCC WICHITA
NOV 12 2015
RECEIVED