

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-113-21255-00-00  
Spot: SWSWNESE Sec/Twnshp/Rge: 7-18S-1W  
1585 feet from S Section Line, 1094 feet from E Section Line  
Lease Name: BURK A Well #: 5  
County: MCPHERSON Total Vertical Depth: 2919 feet

Operator License No.: 5631  
Op Name: LOEWEN OPERATOR, INC.  
Address: 208 S MAIN PO BOX 335  
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2919		100 SX
SURF	8.625	200		140 SX
SURF		205		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/09/2015 12:00 AM  
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.  
Proposal Rcvd. from: VAN C. BACON Company: \_\_\_\_\_ Phone: (620) 654-8116

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: HUNTER CLARK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/18/2015 12:00 AM KCC Agent: HUNTER CLARK

Actual Plugging Report:

HIT BRIDGE @ 1600' GOING TO BRING IN WORK STRING. WASHED DOWN TO TD SAND @ 2716' 5 SKS CAP. RAN TUBING ON 9/17/2015 TO 300' SET 45 SXS. GAS BLEW CEMENT OUT OF HOLE. RAN 1" DOWN BACKSIDE TO 250' PUMPED 65 SXS. RE-RUN TUBING DOWN HOLE TO 300' SET 50 SXS. CIRCUALTE - 0'. PULLED TUBING HOLE STAYED FULL NO TOP OFF NEEDED. 9/18/15 CHECKED TOP PLUG AT SURFACE.

Perfs:


Remarks: TICKET # 46209 CONSOLIDATED EL DORADO

Plugged through: TBG

KCC WICHITA  
NOV 09 2015  
RECEIVED

District: 02

Signed



(TECHNICIAN)

✓/JK