

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-21409-00-00  
Spot: SENWNW Sec/Twnshp/Rge: 35-10S-24W  
4290 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: GEYER Well #: 1-35  
County: GRAHAM Total Vertical Depth: 4300 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4268		225 SX
SURF	8.625	236		210 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/14/2015 9:30 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Perforations at 3804' - 3808', 3896' - 3900', 3956' - 3960'.  
Shot perforations at 2450'.  
Packer stuck in hole at 3777'. Shot off tubing at this point.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/14/2015 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3746' and pumped 20 sx neat cement w/55 sx cement and 200 # hulls. Pulled tubing to 2841' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 1841' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 905' and pumped 100 sx cement. Good circulation of cement. Pulled tubing out and topped off w/25 sx cement. Tied on to backside and squeezed w/100 sx cement w/200 # hulls. Shut in pressure 100 psi. Cement falling will check on 10/15/15.  
10/15/2015- Topped off casing with 14 sx redi mix.  
GPS: 39.14369 -099.97425

Perfs:


Top	Bot	Thru	Comments
3956	3960		
3896	3900		
3804	3808		

Remarks: SWIFT CEMENT TICKET # 28727

Plugged through: TBG

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

CM

KCC WICHITA

NOV 16 2015

RECEIVED

OCT 29 2015

Form CP-2/3