

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-057-20640-00-00  
Spot: NESESW Sec/Twnshp/Rge: 5-25S-23W  
1049 feet from S Section Line, 2355 feet from W Section Line  
Lease Name: WARNER Well #: 5-14  
County: FORD Total Vertical Depth: 4950 feet

Operator License No.: 32204  
Op Name: REDLAND RESOURCES, LLC  
Address: 6001 NW 23RD ST  
OKLAHOMA CITY, OK 73127

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4600		WITH 2 SX CMT
COND	20	51		5.5 YDS.
PROD	4.5	4941	0	WITH 200 SX CMT
SURF	13.375	267		WITH 225 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/03/2015 12:20 PM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 4606' WITH 2 SX CMT. CIRCULATE CMT TO SURFACE FROM 1560'. CHECK BACKSIDE WITH CMT TO 500#.

Plugging Proposal Received By: WADE KLAUS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/03/2015 2:00 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

\*\*PERFORATED AT 765' & CIRCULATED CMT TO SURFACE TO COMPLETE ALT II ON 8/24/09.\*\* CIBP @ 4600' WITH 2 SX CMT ON TOP. RUN TBG TO 1560' & CIRCULATE CMT TO SURFACE WITH 100 SX CMT. TIED ON 4 1/2" X 8 5/8" ANNULUS & PUMPED 15 SX CMT. SHUT IN AT 500#.

Perfs:

Top	Bot	Thru	Comments
4656	4679		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed \_\_\_\_\_

RECEIVED  
NOV - 6 2015  
KCC DODGE CITY

KCC WICHITA

NOV 12 2015

RECEIVED