

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-057-20615-00-00
Spot: SWSWNWSW Sec/Twnshp/Rge: 14-25S-21W
1371 feet from S Section Line, 4986 feet from E Section Line
Lease Name: OFFERLE Well #: 1-14
County: FORD Total Vertical Depth: 4850 feet

Operator License No.: 4067
Op Name: TKO INVESTMENTS, INC.
Address: 10881 W MCARTOR RD
DODGE CITY, KS 67801

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1392		CEMENTED WITH 200 SX CMT. 15 SX CMT CIRCULATED TO PIT.
PROD	4.5	4312	0	WITH 200 SX CMT
SURF	8.625	269		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/04/2015 11:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: J DARYL TIEBEN Company: TKO INVESTMENTS Phone: (620) 225-0263

Proposed Plugging Method: SQUEEZE PERFS WITH 25 SX CMT & 100# HULLS. PLUG AT 1450' WITH CMT TO 0'. CHECK BACKSIDE WITH CMT TO 500#.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/04/2015 12:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

BULLHEADED 25 SX CMT WITH 100# HULLS FOLLOWED BY 40 BBL MUD SPACER THEN 95 SX CMT TO SURFACE. PRESSURED TO 1000#. PRESSURED THE BACKSIDE TO 300# WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4163	4168		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

RECEIVED
NOV - 6 2015
KCC DODGE CITY

Signed



(TECHNICIAN)

KCC WICHITA

NOV 12 2015

RECEIVED