

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21095-00-00
Spot: S2N2SENV Sec/Twnshp/Rge: 27-29S-18W
3523 feet from S Section Line, 3291 feet from E Section Line
Lease Name: HIEBSCH Well #: 1
County: KIOWA Total Vertical Depth: 5080 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 155 N MARKET STE 700
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	5067	1513	WITH 100 SX CMT
SURF	8.625	518		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/29/2015 12:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JEFF WERTH Company: H-D OILFIELD SERVICE Phone: (785) 798-7677

Proposed Plugging Method: PUMP 30 SX CMT WITH 100# HULLS ON BOTTOM OR RUN TBG. PLUG AT 1200' WITH 15 SX GEL & 50 SX CMT. PLUG AT 570' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/29/2015 4:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMPED DOWN 5 1/2" CASING WITH 100# HULLS & 30 SX CMT AT 3.5 BPM AT 600#. DISPLACED CMT TO 4700'. 1ST PLUG AT 1200' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 555' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4978	4987		
4958	4970		
4844	4856		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01
RECEIVED
NOV - 4 2015
KCC DODGE CITY

Signed Stephen J. Pfeifer
(TECHNICIAN)
KCC WICHITA

NOV 12 2015
RECEIVED