

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-097-21220-00-00  
Spot: E2NE Sec/Twnshp/Rge: 17-29S-18W  
4020 feet from S Section Line, 520 feet from E Section Line  
Lease Name: PETERS Well #: 1  
County: KIOWA Total Vertical Depth: 5030 feet

Operator License No.: 5004  
Op Name: VINCENT OIL CORPORATION  
Address: 155 N MARKET STE 700  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4730		WITH 2 SX CMT
CIBP		4869		WITH 2 SX CMT
PROD	4.5	5027	1887	WITH 115 SX CMT
SURF	8.625	319		WITH 175 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/03/2015 10:30 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JEFF WERTH Company: H-D OILFIELD SERVICES Phone: (785) 798-7677

Proposed Plugging Method: CIBP @ 4869' WITH 2 SX CMT. CIBP @ 4730' WITH 2 SX CMT. PLUG AT 1440' WITH 15 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/03/2015 5:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP'S @ 4869' & 4730' WITH 2 SX CMT EACH. 1ST PLUG AT 1440' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 370' WITH 50 SX CMT. 3RD PLUG AT 33' WITH 40 SX CMT. CMT CIRCULATED.

Perfs:


Top	Bot	Thru	Comments
4919	4928		
4823	4826		
4794	4796		
4780	4782		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)



KCC WICHITA

NOV 12 2015

RECEIVED

RECEIVED  
NOV - 4 2015  
KCC DODGE CITY

