

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21235-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 3-29S-18W
987 feet from S Section Line, 2291 feet from E Section Line
Lease Name: BRENT B Well #: 1
County: KIOWA Total Vertical Depth: 5018 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 155 N MARKET STE 700
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3555		WITH 2 SX CMT
CIBP		4776		WITH 2 SX CMT
PROD	5.5	5015	850	WITH 150 SX CMT
SURF	8.625	310		WITH 175 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/28/2015 9:00 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: JEFF WERTH Company: H-D OILFIELD SERVICE, INC. Phone: (785) 798-7677

Proposed Plugging Method: SET CIBP @ 4776' WITH 2 SX CMT. SET CIBP @ 3555' WITH 2 SX CMT. PLUG AT 1260' WITH 12 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/28/2015 3:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

LEFT 695' OF 4 1/2" IN HOLE FROM 595' TO 1280'. SET CIBP @ 4776' WITH 2 SX CMT. SET CIBP @ 3555' WITH 2 SX CMT. CUT CASING AT 1545'. PULLED TO 1290' & PUMPED 12 SX GEL & 50 SX CMT. TRIED TO PULL CASING BUT WAS HUNG UP. CIRCULATED APPROXIMATELY 40 BBL WATER TO FREE UP BUT WOULD NOT MOVE. PUMPED ADDITIONAL 50 SX CMT TO ENSURE ANHYDRITE PLUG. RE-SHOT CASING AT 595'. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4826	4833		
3605	3610		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed

Larry D Harris ECRS
(TECHNICIAN)
JA
KCC WICHITA

RECEIVED
NOV - 4 2015
KCC DODGE CITY

NOV 12 2015
RECEIVED