

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-20676-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 34-21S-15W
4960 feet from S Section Line, 1004 feet from E Section Line
Lease Name: JOHNSTON Well #: 2
County: PAWNEE Total Vertical Depth: 3902 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>30705</u>	PROD	4.5	3901	0	WITH 100 SX CMT
Op Name: <u>YOUNGER ENERGY COMPANY</u>	SURF	8.625	923		WITH 425 SX CMT
Address: <u>9415 E. HARRY STREET, SUITE 403 BU WICHITA, KS 67207</u>					

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/02/2015 9:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: DON BROWNING Company: YOUNGER ENERGY Phone: (316) 681-2542

Proposed Plugging Method: Parted tubing in well @ 2950'. Plug @ 2950' w/20 sxs 60/40 poz followed by 20 sxs 60/40 w/100 lbs hulls. 160 sxs @ 960', circulate cement to surface as required.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/02/2015 12:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

TOP OF PARTED TBG @ 2950'. PERFORATED AT 960'. 1ST PLUG AT 2949' WITH 40 SX CMT & 100# HULLS. PULLED TBG TO 969' & PUMPED 160 SX CMT CIRCULATING CMT UP THE 4 1/2". CLOSED THE CASING VALVE & CONTINUED TO PUMP CMT UP THE ANNULUS BUT PRESSURES GOT TOO HIGH TO CONTINUE. PULLED TBG & STARTED PUMPING CMT DOWN THE CASING & HAD GOOD RETURNS. PUMPED 50 SX CMT & RETURNS SLOWED & QUIT. TIED ONTO THE BACKSIDE & PUMPED 113 SX CMT. PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
3868	3872		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
NOV - 4 2015
KCC DODGE CITY

KCC WICHITA
NOV 12 2015
RECEIVED