

290  
R

5-21-88

1 051056

API NUMBER 15- 047-21,318-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C. SE. SE., SEC. 9, T. 25 S, R. 20 W. EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 9408

660 feet from S section line

660 feet from E section line

Operator: Trans Pacific Oil Corporation  
Name & Address: 410 One Main Place  
Wichita, KS 67202

Lease Name Froetschner Well # 1

County Edwards 167.38

Well Total Depth 5150 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 362

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Trans Pac Drilling, Inc. License Number 5841

Address 410 One Main Place, Wichita, KS 67202

Company to plug at: Hour: 4 a.m. Day: 21 Month: 5 Year: 19 88

Plugging proposal received from Gary Pugh

(company name) Trans Pac Drilling, Inc. (phone) 316-262-3596

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1358-82'

1st plug at 1390' with 50 sx cement, 2nd plug at 700' with 50 sx cement,

3rd plug at 390' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6 a.m. Day: 21 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1390' with 50 sx cement,

2nd plug at 700' with 50 sx cement,

3rd plug at 390' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED  
I did not observe this plugging.

DATE 6-23-88

INV. NO. 20946

Signed Richard W. Lacey (TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 26 1988  
5-26-88  
CONSERVATION DIVISION  
Wichita, Kansas