

1 120187

DEC 16 1988

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,292-00-00

C SE SE, SEC. 29, T 25 S, R 18 W/E

660 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Wilson Well # 1-29

Operator: Murfin Drilling Company

County Edwards 163.67

Name & Address 250 North Water, Suite 300

Well Total Depth 5036 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 272

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 16 Month: 12 Year: 19 88

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4382' PBSD 4328' Perfs at 4236-39'

1st plug sand back to 4180' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Plugging Proposal Received by Richard Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 2:30 p.m. Day: 16 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4180' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-700 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2518' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

If (and) observed this plugging.

Signed *Dean Rankin*  
(TECHNICIAN)

NOTICED  
DATE DEC 22 1988

NO. NO. 23438