

1 040433

6-20

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-20,736-00-00

NE NE SE, SEC. 31, T 25 S, R 17 W/E

2310 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4635

Lease Name Mathes Well # 2

Operator: Great Bend Casing Pullers, Inc.

County Edwards 149.14

Name & Address Box 768

Well Total Depth 4589 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 412

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11:45 a.m. Day: 20 Month: 6 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Behd Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4584' Perfs at 4514-17, 4524-28, 4560-64'

1st plug sand back to 4465' and dump 4 sx cement on top of sand bridge through bailer,
2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 20 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4465' and dumped 4 sx cement on top of
sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 200 psi and shut in 50 psi.

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 1990
6-27-90
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2320' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED (Wichita, Kansas) observe this plugging.

DATE 7-3-90

Signed Stephen J. Pfeifer
(TECHNICIAN)

INV. NO. 28537