

1052406

TO: STATE CORPORATION COMMISSION

API NUMBER 15-047-19,000-0000
C NE NE SEC. 35, T 25 S, R 16 W

CONSERVATION DIVISION - PLUGGING SECTION 4620 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME CUDNEY WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY EDWARDS 145.60

OPERATOR LICENSE # 3911 WELL TOTAL DEPTH 4480 FEET

OPERATOR: RAMA OPERATING CO., INC. PRODUCTION CSG: SIZE 5 1/2" @ 4462' WITH 125 SX

NAME AND PO BOX 159 SURFACE CASING: SIZE 8 5/8" @ 424' WITH 425 SX

ADDRESS STAFFORD, KS 67578

ABANDONED OIL WELL X GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 05 MONTH: 07 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MONTE ANDREWS

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 4367-77, 4337-43, 4012-16

SAND TO 3960' AND 5 SX CEMENT. PUMPED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 970' WITH 10 SX GEL & 50 SX CEMENT. 2ND PLUG AT 460' WITH 50 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT. GOOD CIRCULATION THROUGHOUT CEMENT JOB.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:02 AM DAY: 05 MONTH: 07 YEAR: 2000

ACTUAL PLUGGING REPORT

SAND TO 3960' AND 5 SX CEMENT. PUMPED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 970' WITH 10 SX GEL & 50 SX CEMENT. 2ND PLUG AT 460' WITH 50 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT. GOOD CIRCULATION THROUGHOUT CEMENT JOB.

RECEIVED
STATE CORPORATION COMMISSION
7-10-00
1111 10 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2500' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED
7/13/00
1060055

SIGNED Richard W. Lacey
(TECHNICIAN) FORM CP-2/3

