

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

SEP 30 1963  
 9-30-63  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts.  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Copeland of Western Petroleum Co. Inc. has this date requested permission to plug the following described well:

Mr. Copeland guarantees payment of the plugging fee.

Operator's full Name: Western Petroleum Co. Inc.

Complete Address: 925 Patton Road, Great Bend, Kansas

Lease Name: Hoffman Well No. # 1

Location: C SE NW Sec. 8 Twp. 25 Rge. 17 (E) (W) W

County Edwards Total Depth 4705 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Copeland was instructed to plug the well as follows:

783' of 8 5/8" surface pipe, cemented with 650 sacks.

Fill hole with drilling mud to 300', 1st cementing plug,

1/4 sack hulls, cement with 25 sacks. Fill hole to 40',

2nd cementing plug, 1/4 sack hulls, cement with 10 sacks

to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Arlie Elving  
 Conservation Division Agent