



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 19 1962
 12-19-62
 CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Darrell Kelso of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Darrell Kelso guarantees payment of the plugging fee.

Operator's full Name: Leben Drilling Co. Inc.

Complete Address: 905 Central Bldg. Wichita Kansas

Lease Name: Tubbs Well No. #1

Location: C - NW - SW Sec. II Twp. 25 Rge. 17 (E) (W) W

County Edwards Total Depth 4598 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Kelso was instructed to plug the well as follows:

4598' of 5 1/2" long string cemented with 125 sacks. Plugged back to 4468'. Top of perforation 44455'. Hole sanded to 4450' and 5 sacks cement. 328' of 8 5/8" surface pipe circulated with cement. Filled hole with mud to 200'. 10' rock bridge with 20 sacks cement. Hole filled with mud to 40' and 10' rock bridge with 10 sacks cement to base of cellar.

Very truly yours,

2392' of pipe recovered from hole

Archie Elving
 Conservation Division Agent