

State of Kansas



FORM CP-2

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Gary Pugh of Big Cat Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Edwards Oil Inc.

Complete Address: 1215 E. 30th. Box 206 Hutchinson Kansas 67501

Lease Name: Boguen Well No. 1

Location: NW-NW-NW Sec. 23 Twp. 25 S Rge. 17 W (E) (W)

County: Edwards Total Depth: 4555'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Pugh was instructed to plug the well as follows:

The anhydrite was topped at 1150'. There is 426' of 8 5/8" surface casing cement circulated, 1st plug after circulating heavy mud for 10 min., at 950' with 40 sbp cement. 2nd plug pushed rubber plug to 420' and pumped 35 sbp of cement on top of it. 3rd plug with hole full of heavy mud, 40 to 0' with 10 sbp cement on solid bridge. They pumped 5 sbp in rat hole & 5 sbp of cement in water well. Plugging accomplished by Halliburton Co. out of Pratt Kans.

Very truly yours,

Paul Luthi

Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
10-22-81  
OCT 21 1981

CONSERVATION DIVISION  
Wichita, Kansas