

State of Kansas



15-047-20171-00-00

FORM CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

10-27-1975
5-27-75
CONSERVATION DIVISION
WICHITA, KANSAS

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Michael of Search Drilg Co has this date requested permission to plug the following described well:

Mr. Michael guarantees payment of the plugging fee.

Operator's full Name: Wayne L. Brown & Robert L. Austin

Complete Address: Box 1029 Wichita, KS

Lease Name: Gatterman Well No. 1

Location: G NW/NW Sec. 34 Twp. 25S Rge. 17 (E)(W) W


County: Edwards Total Depth 4523 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Michael was instructed to plug the well as follows:

269 ft 8 5/8 surface cemented with 250 sacks. Fill hole to 250 ft, plug, $\frac{1}{2}$ sack hulls, 25 sacks cement. Mud to 40 ft, plug, $\frac{1}{2}$ sack hulls, 10 sacks cement to surface. 2 sacks cement in rat hole.

Very truly yours,


Conservation Division Agent