



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

RECEIVED
 STATE CORPORATION COM.

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

JUL 20 1962
 7-20-62
 CONSERVATION DIV
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date 7-14-1962, 1961, authorized the following plugging operation:

Operator's full Name: Braden Drilling Co.

Complete Address: 1206 Un. Nat'l Bg., Wichita, Kansas

Lease Name: ~~Gepperman~~ **GATPERMAN** Well No. 1

Location: NE-NE-1/4 NW Sec. 34 Twp. 25 Rge. 17 (E) (W) X

County: Edwards Total Depth: 4670'

Oil Well L Gas Well _____ Input Well _____ SWD Well _____

D & A _____ Other well as hereafter indicated: _____

Abandoned Oil well

Operator was instructed to plug well as follows:

4548' of 5 1/2" pipe. Top perforation 4460'. Sanded to 4400'

and 5 sacks cement. 277' of 8 5/8" surface pipe. Filled

with mud to 250', 10' rock bridge and 20 sacks cement.

Filled with mud to 40', 10' rock bridge and 10 sacks cement

to bottom of cellar.

Very truly yours,

Harman Justus

