

15-047-00275-00-00

FORM - CP-2
Rev. 8-26-62

State of Kansas



JOHN ANDERSON, Jr. Governor
 WILLIAM L. MITCHELL, Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Rec'd
 9-16-64

Called Hershberger ← Responsible for Fee
 James

Dear Sir:

Mr. Bill Walker of Rains & Williamson Oil Co. has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: James W. Hershberger

Complete Address: 807 First National Bank Bldg., Wichita, Ks.

Lease Name: Herrmann Well No. # 1

Location: C SE SW Sec. 19 Twp. 25 Rge. 20 (E) (W) W

County Edwards Total Depth 4800 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

308' of 8 5/8" surface pipe, cement circulated with 175 sacks.
Fill hole with drilling mud to 275', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat with 2 sacks.

Very truly yours,

Archie Elving