

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

AUG 17 1966
8-17-66
CONSERVATION DIVISION
WICHITA, KANSAS

Dear Sir:

Mr. James Shipley of Graybol Oil Corporation has this date requested permission to plug the following described well:

Mr. Shipley guarantees payment of the plugging fee.

Operator's full Name: Graybol Oil Corporation

Complete Address: 2200 National Bank of Tulsa Bldg., Tulsa, Okla.

Lease Name: Boehme Well No. # 1

Location: C NW NW Sec. 8 Twp. 25 Rge. 20 (E)(W) W

County Edwards Total Depth 4765' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Shipley was instructed to plug the well as follows:

305' of 8 5/8" surface pipe, cement circulated with 160 sacks. Fill hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Audie Elving
Conservation Division Agent