

15-155-00388-0000

Recd 11-28-62

NOV 28 1962

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Nov. 25, 1962.

Dear Sir:

Mr. Arland Bruce of E. K. Cary Drilling Co. Inc. has this date requested permission to plug the following described well:

Mr. Arland Bruce guarantees payment of the plugging fee.

Operator's full Name: E. K. Cary Drilling Co. Inc.

Complete Address: Box 620 McPherson Kansas.

Lease Name: Waggoner #1 Well No. #1

Location: C-SW-NW Sec. 15 Twp. 24 Rge. 10 (E) (W) X

County Reno Total Depth 3725 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Arland Bruce was instructed to plug the well as follows:

~~225' of 8 5/8" surface pipe circulated with 225 sacks cement
Hole filled to 180' with heavy drilling mud, 1 sack hulls,
1st cementing plug and 20 sacks cement through drill pipe
by Halliburton. Hole filled to 40' with heavy drill mud,
1/2 sack hulls, 2nd cementing plug and 10 sacks cement to base
of cellar. Rat hole bridged, 2 sacks cement.~~

Very truly yours,

Herman J. Gustafson
Conservation Division Agent