

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-21135-0001

LEASE NAME Hurst

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 4 TWP. 24S RGE. 10W (E) or (W)

COUNTY Reno

Date Well Completed

Plugging Commenced 1-9-03

Plugging Completed 1-13-03

RECEIVED

1-22-03
JAN 22 2003

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

LEASE OPERATOR Lotus Operating Co., LLC

ADDRESS 914 E. Douglas Wichita, Kansas 67202

PHONE/(316) 262-1077 OPERATORS LICENSE NO. 31980

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3851'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	297'	None
				4-1/2"	3725'	2010'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s
Set CIBP @2692' with 4 sacks cement on top. Shot pipe @2200' and 2010', pulled up to
1450', pumped 35 sacks cement, pulled up to 950', pumped 35 sacks cement and 100# bulls,
pulled up to 350' and circulated 130 sacks cement, 60/40 pos, 4% gel.
Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lotus Operating Co., LLC.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 21st. day of January, 2003

[Signature]
Notary Public

My Commission Expires:

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-05

Form 07
Revised 05-

02