

API NUMBER 15-155-21,232-0000

LEASE NAME Cole

WELL NUMBER 1

2970' Ft. from S Section Line

330' Ft. from E Section Line

SEC. 35 TWP. 24 RGE. 9 ~~W~~ W

COUNTY Reno

Date Well Completed 11-28-92

Plugging Commenced 11-28-92

Plugging Completed 11-28-92

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Central Energy Corp.

ADDRESS P. O. Box 47590, Wichita, KS 67201-7590

PHONE#(316) 267-0707 OPERATORS LICENSE NO. 9354

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 27, 1992 (date)

by Mike Wilson (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3944'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	213'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Spotted 35 sx. cement at 1375' thru drill pipe. Spotted 35 sx. cement at 900' thru drill pipe. Spotted 35 sx. cement at 265' thru drill pipe. Spotted 25 sx. cement at 60' w/ wood & rubber plug thru drill pipe. Spotted 15 sx cement in rathole. Spotted 10 sx. cement in mouse hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address P. O. Box 48848, Wichita, KS 67201-8848

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Central Energy Corp.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


Michael L. Considine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Michael L. Considine 1-28-93
 (Address) P. O. Box 48848, Wichita, KS 67201-8848



AND SWORN TO before me this 2nd day of December, 1992
Carolyn J. Tjaden
 Notary Public
 WICHITA, KANSAS

My Commission Expires: _____





WHITE

ANDELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Central Energy Corp., P. O. Box 47590, Wichita, KS 67201-7590

CONTRACTOR: White & Ellis Drilling, Inc. 401 E. Douglas - Suite 500
Wichita, Kansas 67202

Lease Name Cole Well No. 1

Sec. 35 T. 24S R. 9W Spot SE SE NE

County Reno State Kansas Elev. _____

Casing Record:

Surface: 8 5/8" @ 213' with 200 sx.

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 3944'

Drilling Commenced 11-20-92 Drilling Completed 11-28-92

Formation	From	To	Tops	
Cellar	0	5	Lansing/Kansas City	3315
Sand	5	35	Kansas City	3465
Sand & Shells	35	214	KC/BKC	3615
Shales	214	1285	Mississippi	3805
Shales & Lime	1285	1640	Miss/Kinderhook Shale	3865
Lime & Shale	1640	1925		
Shale & Lime	1925	2190		
Lime & Shales	2190	2695		
Shales & Lime	2695	2895		
Lime & Shales	2895	3944		

RECEIVED
STATE CORPORATION COMMISSION
JAN 28 1993
CONSERVATION DIVISION
WICHITA, KANSAS