

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME HORTON
 WELL NUMBER 1-22
1320 Ft. from S Section Line
4220 Ft. from E Section Line
 SEC. 22 TWP. 24S RGE. 9W (W) or (N)
 COUNTY RENO
 Date Well Completed 10-08-94
 Plugging Commenced 7:30 PM
9:30 PM
 Plugging Completed 10-08-94

LEASE OPERATOR STELBAR OIL CORPORATION INC
 ADDRESS 155 N MARKET SUITE 500, WICHITA KS 67202
 PHONE (316) 264-8378 OPERATORS LICENSE NO. 6044

Character of Well _____
 (Oil, Gas, O&A, SWO, Input, Water Supply Well)

The plugging proposal was approved on 10-04-94 (date)
 by Dave Wertz (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? YES

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 3915'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	216'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, - from _____ feet to _____ feet each set
35 sacks at 1400'; 35 sacks at 850'; 35 sacks at 270'; 25 sacks at 60' and 15 sacks in rathole. Used 60/40 Poz 4% gel.


Name of Plugging Contractor STERLING DRILLING COMPANY License No. 5142
 Address P O BOX 129, STERLING KS 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: STELBAR OIL CORPORATION INC.
 STATE OF KANSAS COUNTY OF RICE, ss.

Richard L. Mead (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Richard L. Mead
 Richard L. Mead, Vice President
 (Address) P O Box 129, Sterling, KS 67579

SUBSCRIBED AND SWORN TO before me this 10th day of October, 19 94

 **CHERYL R. DAVIS**
 State of Kansas
 My Appt. Exp. Feb. 15, 1997

Cheryl R. Davis
 Notary Public

My Commission Expires: _____
 USE ONLY ONE SIDE OF EACH FORM

02-15-97

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 10 1994
 WICHITA, KANSAS

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

(316) 278-2131

SAMPLE LOG ----- HORTON #1-22

Located: 1320' FSL & 1060' FWL SW/4 of Sec. 22-24S-9W,
Reno County, Kansas

OWNER: STELBAR OIL CORPORATION INC

ROTARY DRILLING CONTRACTOR: STERLING DRILLING COMPANY

COMMENCED: October 3, 1994

COMPLETED: October 8, 1994

TOTAL DEPTH: 3915' Driller
3915' LoggerLOG0' - 85' Surface Soil and Sand
85' - 220' Red Bed
220' - 775' Clay and Shale
775' - 3799' Lime and Shale
3799' - 3885' Chert Lime and Shale
3885' - 3915' Lime and ShaleCASING RECORD

Spud at 12:15 PM, 10-03-94. Drilled 220' of 12 1/4" hole. Ran 5 joints 8 5/8" 20# surface casing. 204.49' set at 216' K.B. Cemented with 195 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 4:00 PM 10-03-94 by Allied, ticket #6250. Good returns.

Plugged.

DEVIATION SURVEY1/2° @ 220'
1° @ 3799'
1 1/2° @ 3915'RECEIVED
STATE CORPORATION COMMISSION

OCT 13 1994

WILMOTA KANSAS - 10N