

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-21331-0000
LEASE NAME FESLER

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-34
4120' Ft. from S Section Line
3854' Ft. from E Section Line
SEC. 34 TWP. 24S RGE. 9W (~~W~~)
COUNTY Reno

LEASE OPERATOR Stelbar Oil Corporation, Inc. /
Grand Mesa Operating Company
ADDRESS 155 N. Market, Suite 500, Wichita, KS 67202
PHONE: (316) 264-8378 OPERATORS LICENSE NO. 6044
9855
Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 09-06-94
8:30 P.M.
Plugging Commenced 09-06-94
10:30 P.M.
Plugging Completed 09-06-94

The plugging proposal was approved on 09-06-94 8:15 A.M. (date)
by Don Thompson (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 3950'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	230'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, -from ___ feet to ___ feet each set

35 sacks at 1450', 35 sacks at 800', 80 sacks at 280' to surface. Cement circulated.
15 sacks in rat hole.
Used 60/40 Poz, 4% Gel.

Name of Plugging Contractor Sterling Drilling Company License No. 5142
Address P O BOX 129, STERLING KS 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: STELBAR OIL CORPORATION INC.
STATE OF KANSAS COUNTY OF RICE, ss.

Richard L. Mead (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Richard L. Mead
Richard L. Mead, Vice President
(Address) P O BOX 129, STERLING KS 67579

SUBSCRIBED AND SWORN TO before me this 7th day of September, 1994

Cheryl R. Davis
Notary Public

My Commission Expires: 02-15-97

USE ONLY ONE SIDE OF EACH FORM



CHERYL R. DAVIS
State of Kansas
My Appt. Exp. Feb. 15, 1997

RECEIVED
STATE CORPORATION COMMISSION
SEP 13 1994
9-13-94
WICHITA DIVISION
Revised 05-88

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

(316) 278-2131

SAMPLE LOG ----- FESLER #1-34

Located: 1160' FNL & 1426' FWL SW NE SW of Sec. 34-24S-9W,
Reno County, Kansas

OWNER: STELBAR OIL CORPORATION INC

ROTARY DRILLING CONTRACTOR: STERLING DRILLING COMPANY

COMMENCED: September 1, 1994

COMPLETED: September 6, 1994

TOTAL DEPTH: 3950' Driller
3947' LoggerLOG0' - 155' Sand
155' - 235' Red Bed
235' - 590' Red Beds and Shale
590' - 3950' Lime and ShaleCASING RECORD

Spud at 7:30 AM, 09-01-94. Drilled 235' of 12 1/4" hole. Ran 5 joints 8 5/8" surface casing. 218.69' set at 230' K.B. Cemented with 195 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 11:00 AM by Allied, ticket #6752. Good returns.

Plugged.

DEVIATION SURVEY1/2° @ 235'
1° @ 3835'RECEIVED
STATE CORPORATION COM
9-13-94 SEP 13 1994
COMMISSION DIVISION
WICHITA, KANSAS