


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Reno County, Sec. 22 Twp. 22S Rge. (E) 6 (W)  
Location as "NE/CNW/SW" or footage from lines SW NW NE  
Lease Owner Brunson-Spines, Inc.,  
Lease Name Phillips Well No. 2  
Office Address 302 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 6-12-1959  
Application for plugging filed 6-12-1959  
Application for plugging approved 6-12-1959  
Plugging commenced 6-13-1959  
Plugging completed 6-13-1959  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3845 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	263'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Circulated hole with very heavy mud. Laid down drill pipe.

Filled hole to 165'. Pushed plug to 165', covered with 1/2 sack hulls and 20 sx. cement, mixed and poured through 5 x jts. drill pipe. Filled hole to 40' of cellar bottom. Pushed plug to 40', covered with 1/2 sack hulls and 10 sacks cement. Plugged rathole with 2 sacks cement.



(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Brunson-Spines, Inc.  
Address 302 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Ralph B. McLaughlin, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph B. McLaughlin  
Ralph B. McLaughlin, Secy-Treas.  
302 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of June, 1959  
Mary G. LaFollette  
Mary G. LaFollette, Notary Public.

My commission expires June 16, 1963

PLUGGING  
FILE SEC. 22 T. 22 R. 6 W.  
BOOK PAGE 48 LINE 1

15-155-00348-00-00

**BRUNSON-SPINES, INC.**  
Wichita, Kansas

WELL: PHILLIPS #2

SW NW NE

COMMENCED RD: 6-2-59

22-22S-6W.

COMPLETED RD: 6-12-59

RENO COUNTY, KANSAS

TOTAL DEPTH: 3845'

ELEVATION: 1565 RB

CASING: 263' - 10-3/4"  
Surface pipe

CONTRACTOR: BRUNSON-SPINES, INC.

STRATA	DEPTH	TOPS	
Sand	60	Heebner Shale	2662 (-1092)
Shale	170	Douglass Shale	2684 (-1119)
Shale & Shells	500	Douglass Sand	2778 (-1213)
Salt	535	Lansing	2869 (-1304)
Salt w/ strks. shale	790	Mississippi	3515 (-1950)
Shale & Lime	850	Kinderhook Shale	3695 (-2130)
Anhydrite	950	Hunton	3812 (-2247)
Anhydrite & Shale	1020	Maquoketa	3832 (-2267)
Lime & Shale	1190	Total Depth	3845 (-2280)
Lime	1350		
Shale w/ stks. Lime	1745		
Shale & Lime	1880		
Shale	1955		
Shale w/ Lime stks.	2205		
Shale & Lime	2385		
Lime	2635		
Lime & Shale	2892		
Lime	3009		
Sandy Lime	3063		
Lime & Shale	3115		
Lime	3370		
Lime & Shale	3515		
Chert	3559		
Chert & Lime	3658		
Lime	3716		
Shale w/ Lime strks.	3777		
Lime & Shale	3845		

RECEIVED  
STATE CUR  
JUL 20 1959  
WICHITA DIVISION  
Wichita, Kansas

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling report.

BRUNSON-SPINES, INC.

*Ralph B. McLaughlin*  
Ralph B. McLaughlin, Secy-Treas.

Signed and sworn to in my presence this 18th day of June, 1959, by Ralph B. McLaughlin, Secretary-Treasurer of Brunson-Spines, Inc., a corporation of the State of Kansas.

PLUGGING  
FILE SEC. 22T.22R.6W  
BOOK PAGE 48 LINE 1

*Mary G. LaFollette*  
Mary G. LaFollette, Notary Public

My commission expires June 16, 1963.