

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-155-21,279-0000

LEASE NAME CAMPBELL

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1-14

1980 Ft. from (S) Section Line

4620 Ft. from (E) Section Line

SEC. 14 TWP. 24S RGE. 9 (E) or (W)

COUNTY RENO

LEASE OPERATOR CHIEF DRILLING, INC.

ADDRESS 120 S. Market, #300 Wichita, Kansas 67202

PHONE#(316) 262-3791 OPERATORS LICENSE NO. 5886

Date Well Completed _____

Character of Well D&A

Plugging Commenced _____

(Oil, Gas, D&A, SHD, Input, Water Supply Well)

Plugging Completed _____

The plugging proposal was approved on September 14, 1993 (date)

by David Wertz (KCC District Agent's Name).

Is ACO-1 filled? by oper. If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 3910'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
surface		0	280	8 5/8"	280'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

.35 sx. @ 1350', 35 sx. @ 850', 35 sx. @ 330', 25 sx. @ 60', 10 sx. in rat hole

10 sx. in water well

TOTAL: 150 sx 60/40 Poz 4% gel Allied Cementing

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor L. D. Drilling, Inc. License No. 6039

Address R.R. 1 Box 183 B Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chief Drilling, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

L. D. Davis

(Employee of Operator) or (~~OWNER~~) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.

(Signature) L. D. Davis

(Address) R.R. 1 Box 183 B


Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 16th day of September 19 93

Bessie M. DeWerff
 Notary Public
 Wichita, Kansas

My Commission Expires: 5-20-97

Bessie M. DeWerff



DRILLER'S WELL LOG

DATE COMMENCED: 9-07-93
 DATE COMPLETED: 9-14-93

0 - 70 Surface
 70 - 280 Red Bed
 280 - 1435 Sand & Shale
 1435 - 3910 Lime & Shale
 3910 RTD

CHIEF DRILLING, INC.
 CAMPBELL #1-14
 C NW SW Sec. 14-T24S-R9W
 RENO COUNTY, KANSAS

ELEVATION: 1656' GR 1661' KB

FORMATION DATA: (Sample)

Tarkio	2390 (-729)
Elmont	2450 (-789)
Howard	2607 (-946)
Topeka LM	2720 (-1059)
Heebner Sh.	3057 (-1396)
Toronto	3071 (-1410)
Douglas Sh.	3079 (-1418)
Brown Lm.	3246 (-1585)
Lansing	3269 (-1608)
Stark Sh.	3538 (-1877)
BKC	3633 (-1972)
Mississippi	3759 (-2098)
RTD	3910

CASING:

Surface-8 5/8" set @ 280' W/185 sx.
 60/40 Pozmix, 2% Gel, 3% cc


A F F I D A V I T

STATE OF KANSAS)
 COUNTY OF BARTON)^{ss}

L. D. DAVIS of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

L. D. Davis
 L. D. Davis

Subscribed and sworn to before me this 16th day September, 1993.



My Commission expires: 5-20-97

RECEIVED
 STATE CORPORATION COMMISSION
 9-20-93
 SEP 20 1993

Bessie M. DeWitt
 Notary Public: Bessie M. DeWitt
 CONSERVATION DIVISION
 KANSAS