

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

15047-2077-0005

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Edwards SEC. 18 TWP. 26S RGE. 20W E/W
 Location as in quarters or footage from lines:

SE SW SE

Locate Well
 correctly on above
 Section Platt.

Lease Owner Texas Energies, Inc.

Lease Name Wetzel Well No. #1

Office Address P.O. Box 947 Pratt, Kansas 67124

Character of Well (Completed as Oil, Gas or Dry Hole): _____

Date Well Completed _____

Application for plugging filed _____

Plugging commenced 7-30-81

Plugging completed 8-6-81

Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz

Producing formation _____ Depth to top _____ bottom _____ T.D. 4770

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	425'	none
				4-1/2"	4762	2615

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Moved on location, checked hole, ran sand to 4700' and dumped
four sacks cement. Pulled 23" tension. Shot and worked pipe
@4005', 3820', 3605', 3420', 3205', 3040', 2920', 2800', 2700'
and 2610'. Pulled 83 joints. Squeezed hole with 15 sacks gel, 6 sacks hulls,
and 10 sacks gel. Released plug and displaced with 150 sacks 50/50 pos
4% gel and 3% cc. Plugging Completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
R. Darrell Kelso
 (Address)

SUBSCRIBED AND SWORN TO before me this 10th day of August, 19 81

My Commission expires:



RECEIVED
 STATE CORPORATION COMMISSION
 Notary Public.

AUG 12 1981
 8-12-81
 CONSERVATION DIVISION
 Wichita, Kansas

GABBERT-JONES, INC.
DRILLERS' WELL LOG
WICHITA, KANSAS

15-847-20277-0000

Wetzel #1
Se SW SE Sec 18-26S-20W
Edwards County Kansas

Commenced: 7-26-77

Completed: 8-6-77

OPERATOR: TEXAS ENERGIES, INC.

Depth		Formation	Remarks
From	to		
0	429	Sand-Shale	Ran 11 jts of 28# 8 5/8" csg
429	705	Sand-Shale	set @ 425' Cemented w/
705	1275	Shale-Redbed	350 sks Common 2% Gel
1275	1922	Shale	3% CC PD @ 4:00 p.m.
1922	2410	Shale-Shells	7-27-77
2410	2580	Shale-Lime	
2580	4286	L.me-Shale	
4286	4770	Lime	Ran 153 jts of 9 1/2# 4 1/2" csg
			set @ 4762' w/10 bbl
			Salt Flush - 125 sks
			Common 10% Salt
			PD @ 8:30 p.m.
			8-6-77
	4770 - TD		

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK):

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
JAMES S. SUTTON II

Subscribed and sworn to before me this 12th day of August, 1977.

Elizabeth J. Edwards
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.

RECEIVED
STATE CORPORATION COMMISSION

SEP 21 1981

CONSERVATION DIVISION
Wichita, Kansas



Wetzel Tech