


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Edwards County, Sec. 32 Twp. 26S Rge. 20W (E) (W)
Location as "NE/CNW&SW&" or footage from lines C NW NE
Lease Owner Walters Drilling Co., & Mull Drilling Co., Inc.
Lease Name Einsel-Edwards Well No. 1
Office Address 400 Insurance Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-19-66 19
Application for plugging filed 10-19-66 19
Application for plugging approved 10-19-66 19
Plugging commenced 10-19-66 19
Plugging completed 10-19-66 19
Reason for abandonment of well or producing formation commercial quantities of oil not found
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4933 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	565'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug @ 400' w/ 25 sx. cement through drill pipe
2nd plug @ 40' w/ 10 sx. cement
2 sx. for rathole

RECEIVED
STATE CORPORATION COMMISSION

OCT 21 1966

10-21-66

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Walters Drilling Co.
Address 400 Insurance Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Robert F. Walters (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert F. Walters
400 Insurance Building, Wichita, Kansas
(Address)

Subscribed and sworn to before me this 21st day of October, 1966

My commission expires October 4, 1967
Juanita M. Green Notary Public.



DRILLER'S LOG

15-047-30072.0000

COMPANY: WALTERS DRILLING CO. & MULL DRILLING CO., INC.
 400 INSURANCE BUILDING
 WICHITA, KANSAS

WELL NAME: EINSEL-EDWARDS #1
 C NW NE SEC. 32-26S-20W
 EDWARDS COUNTY, KANSAS

CONTRACTOR: WALTERS DRILLING CO.
 400 INSURANCE BUILDING
 WICHITA, KANSAS

ROTARY DRILLING COMMENCED: OCTOBER 6, 1966
 ROTARY DRILLING COMPLETED: OCTOBER 19, 1966

ELEVATION: 2267 KB

CASING RECORD: 8 5/8" @ 565' w/ 275 sacks cement

LOG

0 - 60	Sand
60 - 560	Shale
560 - 575	Sand
575 - 720	Shale
720 - 735	Anhydrite
735 - 1085	Shale
1085 - 1455	Shale and Lime
1455 - 1562	Shale and Shells
1562 - 1890	Lime and Shale
1890 - 2350	Shale
2350 - 2640	Lime and Shale
2640 - 2910	Lime
2910 - 3025	Lime and Shale
3025 - 3210	Shale and Lime
3210 - 3380	Lime and Shale
3380 - 3888	Shale and Lime
3888 - 4220	Lime and Shale
4220 - 4660	Lime
4660 - 4708	Lime and Shale
4708 - 4933	Lime
4933	<u>Rotary Total Depth - D & A</u>


The undersigned, Robert F. Walters, hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

BY Robert F. Walters
ROBERT F. WALTERS, Partner

Subscribed and sworn to before me
this 21st day of October, 1966.

Juanita M. Green
 Juanita M. Green, Notary Public
 My Commission Expires: October 4, 1967



RECEIVED
STATE CORPORATION COMMISSION

OCT 21 1966

CONSERVATION DIVISION
Wichita, Kansas