

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-42-3-117

API NUMBER 15-057-20520-6000

LEASE NAME KLENKE

WELL NUMBER #1

1700 FT. from S Section Line

1480 FT. from E Section Line

SEC. 5 TWP. 26 (CGE. 21) (X) or (W)

COUNTY FORD

Date Well Completed 10-7-93

Plugging Commenced 10-7-93

Plugging Completed 10-7-93

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR SID TOMLINSON

ADDRESS 1802 Wildwood Drive Stillwater, OK. 74075

PHONE (405) 372-2833 OPERATORS LICENSE NO. 6412

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 7, 1993 (Date)

by Steve Middleton Dist.#1 Dodge City, Ks: (KCC District Agent's Name)

is ACO-1 filled? by operator if not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4890'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|--------------|------|------|--------|--------|------------|
| | surface csg. | 0 | 415' | 8 5/8" | 415' | none |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section.

50 sx. @ 1410', 40 sx. @ 700', 50 sx. @ 435', 10 sx. @ 40', 15 sx. in rathole
TOTAL 165 sx. 60/40 Pozmix, 6% Gel (Allied Cementing Service)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor L. D. Drilling, Inc. License No. 6039

Address R.R. 1 Box 183 B Great Bend, KS. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Sid Tomlinson

STATE OF Kansas COUNTY OF Barton, ss.

L. D. Davis (Employee of Operator Wichita, Kansas)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed. That the same are true and correct, so help me God.


(Signature) L. D. Davis

(Address) R.R. 1 Box 183 B Gt. Bend, KS. 67530

SUBSCRIBED AND SWORN TO before me this 13th day of October, 1993

Bessie M. DeWerff
 Notary Public
 Bessie M. DeWerff

My Commission Expires: 5-20-97



15-057-26576-000

DRILLER'S WELL LOG

DATE COMMENCED: 9-27-93
DATE COMPLETED: 10-07-93

SID TOMLINSON
KLENKE #1
App. NE-SW-NE SEC. 5-T26S-R21W
FORD COUNTY, KANSAS

- 0 - 415 Surface Shales
- 415 - 720 Sand & Shale
- 720 - 1367 Shale
- 1367 - 1406 Anhy
- 1406 - 1995 Shales
- 1995 - 2540 Shale & Lime
- 2540 - 4485 Lime & Shale
- 4485 - 4600 Lime
- 4600 - 4792 Lime & shale
- 4792 - 4890 Lime
- 4890 RTD

ELEVATION: 2320' GR 2325' KB

SURFACE CASING:

8 5/8" set @ 415' W/250 sx. 60/40
Pozmix, 2% Gel, 3% cc


A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON)^{SS}

L. D. DAVIS of lawful age, does swear and state that the facts
and statements here-in are true and correct to the best of his knowledge.

L. D. Davis
L. D. Davis

Subscribed and sworn to before me this 13th day of October, 1993.



Bessie M. DeWette
Notary Public: Bessie M. DeWette

My Commission expires: 5-20-97

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1993
CONSERVATION DIVISION
Wichita, Kansas