


15-047-20727-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Edwards County, Sec. 25 Twp. 26S Rge. 17W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
440' ENL; 440' FEL, NW/4
Lease Owner F. G. Holl
Lease Name Hagewood #1-25 Well No. 1-25
Office Address 6427 East Kellogg, Wichita, Kansas 67207
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed September 5, 1980
Application for plugging filed September 5, 1980
Application for plugging approved September 5, 1980
Plugging commenced 8:30 AM September 5, 1980
Plugging completed 10:15 AM September 5, 1980
Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation Depth to top Bottom Total Depth of Well 4645'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	364'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Filled hole with heavy mud.
Plugged through open ended drill pipe
50 sacks at 600'; 40 sacks at 360'.
Filled hole with heavy mud, bridge and
plug with 10 sacks at 40', 5 sacks in
rathole by Howco.

9-24-80
RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1980
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KXXK KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of September, 19 80.



Charles M. Hall
Charles M. Hall, Notary Public.

My commission expires

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

15-047-20727-0000

WELL LOG - - - - - HAGEWOOD #1-25
Located: 440' ENL; 440' FEL, NW/4, Section 25-26S-17W,
Edwards County, Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: August 27, 1980
COMPLETED: September 5, 1980

TOTAL DEPTH: 4645'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 264 Surface Soil and Sand	Ran 8 joints used 28 $\frac{1}{2}$, 8 5/8" casing,
264 - 367 Shale	351.99' set at 364' K.B. with 300
367 - 460 Shale and Sand	sacks 60/40 Pozmix with 3% cc. Plug
460 - 1080 Red Beds and Shale	down at 4:15 PM, 8-27-80, by Howco.
1080 - 1087 Anhydrite	
1087 - 1450 Shale	
1450 - 4390 Lime and Shale	
4390 - 4582 Lime	
4582 - 4645 Lime and Shale	Plugged.

9-24-80
RECEIVED
STATE CORPORATION COMMISSION
1 SEP 24 1980
CONSERVATION DIVISION
Wichita, Kansas

Deviation Surveys: 1° at 2314
1° at 4582