

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-547-210(a)-0000

LEASE NAME Hagewood

WELL NUMBER _____

_____ Ft. from S Section Line

_____ Ft. from E Section Line

SEC. 25 TWP. 26 SRGE. 17 (E) or (W)

COUNTY Edwards

Date Well Completed 9/15/82

Plugging Commenced 4/12/89

Plugging Completed 4/20/89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR W.L. Kirkman Inc.

ADDRESS P.O. Box 782290
Wichita, KS 67278-2290

PHONE# (316) 685-5372 OPERATORS LICENSE NO. 5673

Character of Well Oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved RECEIVED _____ (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, MAY 19 1989 well log attached? _____

Producing Formation _____ Top _____ Bottom _____ T.D. 4742'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	339	none
				4 1/2	4741	2827

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged bottom with 35 sacks cement mixed with 100# hulls to 4200',
shot @3541', 3022', 2827', pulled pipe, plugged surface with 400# hulls,
10 gel, 50 sacks cement, 10 gel, 100# hulls, 8 5/8" plug, 120 sacks
60/40 poz 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: W.L. Kirkman Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 18th day of May, 19 89

James Hoover
Notary Public

My Commission Expires: _____



15.047-21069-0000

OPERATOR: W. L. KIRKMAN, INC.
CONTRACTOR: ALDEBARAN DRILLING CO., INC.

COMMENCED: 9-6-82
COMPLETED: 9-15-82
CASING RECORD:
8 5/8" at 339'
4 1/2" at 4741'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
RED BED AND SHALE	0	600'
RED BED	600'	1090'
SHALE	1090'	1819'
SHALE AND LIME	1819'	4742'

RECEIVED
STATE CORPORATION COMMISSION

APR 5 1989

4-5-89

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I certify that this is a true and correct copy of the Driller's Log on the well drilled NW/4 Sec. 25-26S-17W, Edwards County Kansas to the best of my knowledge and belief.

ALDEBARAN DRILLING CO. INC.

Kirby C. Evers

Kirby C. Evers, Vice President

Subscribed and sworn to before me this 17th Day of September 1982.

