

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Edwards County. Sec. 21 Twp. 26S Rge. (E) 17 (W)
Location as "NE/CNW/SW" or footage from lines. NW NE
Lease Owner Glenn N. Rupe
Lease Name FISHER Well No. 1
Office Address 222 Brown Building - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-2 19 68
Application for plugging filed 11-2 19 68
Application for plugging approved 11-2 19 68
Plugging commenced 11-2 19 68
Plugging completed 3:00 AM 11-3 19 68
Reason for abandonment of well or producing formation No oil or gas found
in commercial quantities.
If a producing well is abandoned, date of last production -- 19 --
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4730 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	329'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud back to 600'. Set plug and 50 sacks cement. Mud back to 300', set plug and 25 sacks cement. Mud back to 40', set solid bridge and capped with 10 sacks, 2 sacks in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
NOV 18 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rains & Williamson Oil Co., Inc.
Address 1425 Wichita Plaza - Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains Wilson Rains
1425 Wichita Plaza - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7 day of November, 19 68

My commission expires June 30, 1971

Sherry Gish Notary Public.

ROTARY DRILLING LOG

Operator: Glenn N. Rupe
FISHER #1
NW NE 21-26S-17W
Edwards County, Kansas

Contractor: Rains & Williamson
Oil Co., Inc.

Commenced: 10-23-68

Completed: 11-2-68

Casing: 8-5/8" @ 329'/250 sx.

Formations

Sand	230'
Shale	465'
Red Bed	540'
Shale	566'
Blaine Anhydrite	578'
Shale	1172'
Anhydrite	1186'
Shale	1835'
Shale and Lime	2213'
Lime and Shale	4110'
Lime	4730'


Rotary Total Depth (D&A) 4730'

15-047-20041-0000


RECEIVED
STATE CORPORATION COMMISSION
NOV 18 1968
CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is
true and correct to the best
of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.


Wilson Rains

Subscribed and sworn to before me, a Notary Public within and for the State
of Kansas, County of Sedgwick, this 7th day of November, 1968.


Sherry Gish Notary Public

My Commission Expires:
June 30, 1971