

WELL PLUGGING RECORD

Give All Information Completely  
in the Required Affidavit  
and Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Edwards County, Sec. 18 Twp. 26S Rge. 17W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SE NW

Lease Owner Phillips Petroleum Company

Lease Name Carl Well No. C-#1

Office Address Box 287, Great Bend, Kansas, Attn M. E. Michael

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-22-63 19

Application for plugging filed 12-22-63 19

Application for plugging approved 12-22-63 19

Plugging commenced 12-22-63 19

Plugging completed 12-22-63 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4625' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	352.75'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud to 300' Plug & 1/2 sk. hulls and 35 sacks cement

Mud to 40' Plug & 1/2 sack hulls & 10 sks. cement

5 sacks in rathole.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 27 1963

12-27-63

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.

Address P. O. Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Leslie Kite (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of December, 1963

My commission expires April 1, 1967

Ulanda Nichols Notary Public.

DRILLER'S LOG

COMPANY: Phillips Petroleum Company  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: CARL C-#1  
 LOCATION: C SE NW Sec. 18-26S-17W  
 EDWARDS COUNTY, KANSAS  
 COMMENCED: 12-6-63  
 COMPLETED: 12-22-63

15-647-10089-0000

0	230	Sand
230	357	Shale
357	640	Shale & Clay
640	890	Shale
890	1150	Anhydrite
1150	1910	Shale & Shells
1910	2210	Shale
2210	2305	Shale & Lime
2305	2635	Lime & Shale
2635	2943	Lime
2943	3206	Lime & Shale
3206	3360	Shale & Soil with Lime
3360	3626	Lime & Shale
3626	3755	Shale & Lime
3755	4002	Lime & Shale
4002	4095	Shale & Lime
4095	4206	Lime
4206	4357	Lime & Shale
4357	4560	Lime
4560	4602	Lime & Shale
4602	4625	Chert & Lime
	<u>4625</u>	<u>Rotary Total Depth - D. &amp; A.</u>

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 27 1963  
 12-27-63  
 CONSERVATION DIVISION  
 Wichita, Kansas

Set 8 5/8" 20# new surface casing @ 352.75' K.B.M. with landing joint  
 Cemented with 150 sacks 20% Diacel "D" with 300# c.c. followed with  
 50 sacks Common with 100# c.c.

I, Leslie Kite, do hereby certify that the above and foregoing is a  
 true and correct copy of the log of the Carl C-#1 well, located C SE NW  
 of Section 18, Township 26 South, Range 17 West, Edwards County, Kansas,  
 as reflected by the files of Leben Drilling, Inc.

*Leslie Kite*

Leslie Kite

STATE OF KANSAS )  
 )SS  
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and  
 for Barton County, Kansas, this 24th day of December, 1963.

*Ulanda Nichols*

Ulanda Nichols, Notary Public

My Commission Expires:  
 April 1, 1967