

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-20302-0000

LEASE NAME Meyers

WELL NUMBER 1-18

         Ft. from S Section Line

         Ft. from E Section Line  
C/S/2 S/2 NE

SEC. 18 TWP. 26 RGE. 17W(E) or (W)

COUNTY Edwards

Date Well Completed         

Plugging Commenced 1-28-88

Plugging Completed 2-3-88

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Murfin Drilling Company

ADDRESS 250 N. Water Suite 300  
Wichita, Kansas 67202

PHONE#(316) 267-3241 OPERATORS LICENSE NO. 6033

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4671'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	282'	none
				4-1/2"	4660'	2404'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4475' and 4 sacks cement. Shot pipe @2735', 2514', 1404', pulled a total of 57 joints of 4-1/2" casing. Plugged surface with 4 hulls, 10 gel, 50 cement, 10 gel, 1 hull, released plug and 125 cement, 60/40 pos, 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 8th day of February, 1988

My Commission Expires:



No FEEVE PUBLICATION COMMISSION

2-10-88  
FEB 10 1988 Form CP-4  
Revised 07-86

CONSERVATION DIVISION  
Wichita, Kansas

GABBERT-JONES, INC.  
 WICHITA, KANSAS  
 DRILLERS' WELL LOG

Myers "B" 1-18  
 1150' FWL & 400 FSL SW/4 Sec 18-26S-17W  
 Edwards County Kansas

15-047-20302-0000

Commenced: 11-15-77

Completed: 11-28-77

OPERATOR: MURFIN DRILLING CO.

From	Depth to	Formation	Remarks
0	103	Sand	Ran 7 jts of 28# 8 5/8" csg
103	285	Sand-Shale	set @ 282' Cemented w/
285	1015	Shale-Sand-Redbed	250 sks Common 2% Gel
1015	1540	Shale-Sand	3% CC
1540	2006	Shale-Lime	PD @ 7:30 p.m. 11-15-77
2006	4035	Lime-Shale	
4035	4670	Lime	
	4670 - TD		Ran 112 jts of 10 1/2" 4 1/2" csg set @ 4660' cemented w/100 sks Class A w/10% Salt 3/4 of 1% CFR-2 2/75 sks Class A Latex PD @ 7:30 p.m. 11-28-77

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

*James S. Sutton II*  
 JAMES S. SUTTON II

Subscribed and sworn to before me this 1st day of December, 1977.

*Elizabeth J. Edwards*  
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.



PROCESSED  
 12-22-87  
 DEC 20 1987  
*Elizabeth J. Edwards*  
 Notary Public