

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Edwards County, Sec. 14 Twp. 26 Rge. 17 (E) (W)

Location as "NE/CNW%SW%" or footage from lines SW SW SE

Lease Owner T. L. Nutt

Lease Name FISHER Well No. 1

Office Address BOX 562 Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed _____ 19__

Application for plugging filed _____ 19__

Application for plugging approved _____ 19__

Plugging commenced 9-20-62 _____ 19__

Plugging completed 10-1-62 _____ 19__

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH

Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4689 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	308'	- NONE -
				5 1/2"	4688	3464

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug bottom - push plug 4500' - 4510'

Rock bridge and 5 sacks cement 4490'

Mud to 300' and 10', Rock Bridge to 290' and 20 sacks cement.

Mud to 40' and 10'. Rock bridge to 30' 10 sacks cement.

Capped - Plugged 2:30 p.m. 9-29-62.

RECEIVED
STATE CORPORATION COMMISSION
NOV 9 1962

CONSERVATION DIVISION
Wichita, Kansas
11-9-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PIPE PULLERS, INC.

Address Box 486 Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Dean Wells (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Wells

P. O. Box 486 Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of October, 19 62

I. J. Rader
Notary Public.

My commission expires July 7, 1964

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY
15-047-00212-0000

Company- STRATA DRILLING & JOHN JENNINGS
Farm- Fisher No. 1

SEC. 14 T. 26 R. 17W
SW SW SE

Total Depth. 4690'
Comm. 2-9-59 Comp. 3-1-59
Shot or Treated.
Contractor. Strata Drlg., Inc.
Issued: 6-6-59

County Edwards
KANSAS



Elevation. 2115' RB

Production. 40 BOPD & 1,000,000
CFG

CASING:

8 5/8" 308' cem w/225 sx.
5 1/2" 4688' cem w/100 sx.

Figures indicate Bottom of Formations.

surface soil & sand	190
shale	210
shale & shells	425
red bed	454
shale	1350
shale & shells	2030
shale & lime	3637
chalky shale & lime	3820
lime & shale	4287
lime	4495
cherty lime	4562
lime & shale	4610
lime, shale & sand	4641
lime, shale & chert	4664
lime	4690
Total Depth	

TOPS:

Heebner	3851
Brown Lime	3985
Lansing	4000
Cherokee	4478
Mississippi	4504
Kinderhook	4587
Viola	4649

DST #1 4462-4495', op 40 mins, weak blow
for 17 min, rec. 15' mud. BHP 0#.

DST #2 4518-4545', op 1 hr, gas to
surf in 3 min., spray of oil in 20 mins.
Rec. 600,000 CF of gas, 240' gas cut mud,
slightly oil specked. BHP 1280#/20 mins.

DST #3 4592-4610', op 1 hr, shut for 20
mins. Rec. 90' mud. BHP 1065#.

DST #4 4636-4669', op 30 mins, wk bl 12
mins. BHP 940#/20 mins.

RECEIVED
STATE CORPORATION COMMISSION

NOV 9 1962

11-9-62

CONSERVATION DIVISION
Wichita, Kansas