

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

Well Plugging Record  
K.A.R. -82-3-117

API NUMBER 15-047-214200000  
LEASE NAME Parker  
WELL NUMBER 1-13

TYPE OR PRINT

NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

1420 Ft. from S (N) Line of Section (Circle one)  
1150 Ft. from E (W) Line of Section (Circle one)

LEASE OPERATOR Lebsack Oil Production, Inc. SPOT LOCATION 170' West and 100' S of C NW/4  
ADDRESS P.O. Box 489 Section 13 Township 26s Range 17w  
CITY, STATE, ZIP Hays Kansas 67601-0489 County Edwards  
PHONE # (913) 625-5444 Date Well Completed February 5, 1997  
Character of Well Dry and Abandoned Date Plugging Commenced February 5, 1997  
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed February 5, 1997

The plugging proposal was approved on January 30, 1997 (date)  
by Kevin Straub (KCC District Agent's Name)  
Is ACO-1 Filed? ? If not, is well log attached? Yes  
Producing Formation(s) D&A Depth to Top Bottom T.D. 4670  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	195	and		
Shale	Shale	195	445	8-5/8"	428.36	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Heavy mud to 1160' then 50 sacks, heavy mud to 450' then 40 sacks, heavy mud to 40' then 10 sacks. Using 60/40 Poz with 6% Gel. Plug rathole with 15 sacks and plug mousehole with 10 sacks.

(If additional description is necessary, use BACK of this form)

Name of Plugging Contractor Sterling Drilling Company  
Licence No. 5142  
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124  
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lebsack Oil Production, Inc. (Operator)

3-4-97

STATE OF KANSAS COUNTY OF PRATT, ss.

Steve E. McClain, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
(Steve E. McClain, President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 3rd day of March 19 97



[Signature]  
(Notary Public)

RECEIVED  
KANSAS CORP COMM  
1997 MAR -4 P 1:19

My Commission Expires: \_\_\_\_\_

15-047-21420-0000

# Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006

Office Phone (316) 672-9508, Fax 672-9509

## SAMPLE LOG

Parker 1-13

**LOCATION:** 170' West and 100' South of C Section 13 T 26S R 17W  
Edwards County, Kansas

**OWNER:** Lebsack Oil Production, Inc.  
**CONTRACTOR:** Sterling Drilling Company, Rig #4

**COMMENCED:** 28-Jan-97  
**COMPLETED:** 04-Feb-97

**TOTAL DEPTH:** DRILLER 4670 FEET  
LOGGER 4669 FEET

### LOG

0	-	195 FEET	Top Soil and Sand
195	-	445 FEET	Shale
445	-	1140 FEET	Clay and Sandstones
1140	-	1155 FEET	Anhydrite
1155	-	4515 FEET	Lime and Shale
4515	-	4574 FEET	Chert
4574	-	4669 FEET	Shale and Sandstone and Chert

### CASING RECORDS

SPUD @ 9:45 am on 1-28-97. Drilled 12-1/4" hole to 445'. Ran 10 joints of New 23# 8-5/8" surface casing, 428.36' set at 442'KB. Cemented with 275 Sacks 60/40 Poz, 2% Gel, 3% CC. Plug down @ 5:00pm 1-28-97 by Allied with good returns, Ticket # 4798.

The well was plugged by Allied, ticket # 4750.

Heavy mud from 4670' to 1160' then 50 sacks,  
heavy mud to 450' then 40 sacks,  
heavy mud to 40' then 10 sacks,  
15 sacks in the rathole and 10 sacks in the mousehole.

Plug down at 4:45 am on 2-5-97 using 60/40 Poz, 6% Gel.

Plugging orders received from Kevin Straub on 1-30-97.

### DEVIATION SURVEYS

3/4 DEG. @ 445 FEET  
1-1/2 DEG. 4540 FEET

3-4-97  
RECEIVED  
KANSAS CORP COMM  
1997 MAR -4 P 1:19