

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-21,249-000

LEASE NAME Rose Mathes

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1-13

SPOT LOCATION C NE NW

SEC. 13 TWP. 26S RGE. 17 (XXX(W))

LEASE OPERATOR F. G. Holl  
6427 East Kellogg  
ADDRESS Wichita, Kansas 67207

COUNTY Edwards

Date Well Completed 4-13-85  
7:00 AM

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Plugging Commenced 4-13-85

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-13-85  
9:15 AM

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District No. 1

Is ACO-1 filed?                      If not, is well log attached? Yes

Producing formation                      Depth to top                      bottom                      T.D. 4645'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	436'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud plugged through open ended drill pipe; 50 sacks at 1130'; 50 sacks at 480'; 1/2 sack hulls, plug and 10 sacks at 40'. 15 sacks in rathole. Used 60/40 Pozmix plus 2% gel (4% total) and 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142  
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED  
STATE CORPORATION COMMISSION

4-18-85 APR 18 1985  
CONSERVATION DIVISION  
WICHITA, KANSAS

STERLING DRILLING COMPANY

(Signature) F. A. Wuellner  
F. A. Wuellner, Secretary

(Address) P. O. Box 129, Sterling, Ks 67579

SUBSCRIBED AND SWORN TO before me this 15th day of April, 1985

Agnes D. Wurst  
Agnes D. Wurst, Notary Public



My Commission expires: 4-6-89

# STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

15-047-21249-0000

WELL LOG - - - - - ROSE MATHES #1-13

Located: C NE NW, Section 13-26S-17W, Edwards County,  
Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 7, 1985

COMPLETED: April 13, 1985

TOTAL DEPTH: 4645'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 225 Sand	Ran 10 joints new 8 5/8", 23# casing. 324.29' pipe set at 436' K.B.
225 - 439 Clay and Shale	Cemented with 350 sacks 60/40 Poxmic plus 3% cc. Plug down at 12:15 PM, 4-7-85, by Howco.
439 - 910 Shale and Sand	
910 - 1133 Shales and Red Beds	
1133 - 1146 Anhydrite	
1146 - 2248 Shale and Lime Stringers	
2248 - 4645 Lime and Shale	Plugged.

Deviation Surveys: 1/4° at 2248'  
1° at 4545'

RECEIVED  
STATE CORPORATION COMMISSION

APR 18 1985  
CONSERVATION DIVISION  
Wichita, Kansas