


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Edwards County, Sec. 12 Twp. 26 Rge. 17 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner Trans Era Petroleum, Inc.
Lease Name Sherman Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3/19/55 19
Application for plugging filed 3/17/55 19
Application for plugging approved 3/17/55 19
Plugging commenced 3/18/55 19
Plugging completed 3/18/55 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4900 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	315°	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud to 300°, set first plug with one-fourth sack of hulls and 20 sacks of cement mixed and run through drill pipe. Filled hole with mud to 35°, set second plug with one-fourth sack of hulls and 10 sacks of cement used.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Trans Era Petroleum, Inc.
Address Russell, Kansas


STATE OF KANSAS, COUNTY OF RUSSELL, ss.
H. R. Michaelis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. R. Michaelis
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of April, 19 55

My commission expires 1-30-57

Margie Cooper
Notary Public.



APR - 5 1955
4-5-55
CONSERVATION DIVISION
Wichita, Kansas

Trans Era Petroleum, Inc.
Sherman #1

NN NN SW 12-26-17N
Edwards County, Ks.

Total Depth: 4900'
Comm. 3/1/55
Comp. 3/19/55

15-047-00088-6000

Casing

8 5/8" Set @ 315'

Cement

225 sacks of Lehigh

FORMATION

DEPTH

Sand	190
Shale	475
Sand	525
Sand-red bed	785
Red bed-shale	1130
Anhydrite	1165
Shale-shells	1265
Shale	1540
Salt	1575
Shale	1720
Shale-lime	2220
Lime	2490
Lime-shale	2720
Lime	2805
Shale-lime	3260
Shale	3300
Lime-shale	3525
Shale	3560
Lime-shale	3985
Lime	4567
Sand-shale	4610
Viola	4660
Lime	4812
Shale-sand	4870
Lime	4900'

STATE OF KANSAS }
RUSSELL COUNTY } ss

I hereby certify that the above information is true and correct to the best of my knowledge.

Caro Betz

Subscribed and sworn to before me this 1st day of April, 1955.

Margie Cooper

Notary Public

My commission expires: 1-30-57.

4-5-55

PLUGGING
FILE SEC 12 26 17W
BOOK PAGE 106 LINE 6