


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Flat

Edwards County, Sec. 9 Twp. 26 Rge. 17 (E) (W)  
Location as "NE/CNW/SE" or footage from lines SE SE SE  
Lease Owner Trans Era Petroleum, Inc.  
Lease Name Fatzner Well No. 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 4/8/55 19  
Application for plugging filed 4/7/55 19  
Application for plugging approved 4/7/55 19  
Plugging commenced 4/8/55 19  
Plugging completed 4/8/55 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4940 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	357	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud to 330', 1/4 sacks hulls and 20 sacks cement through drill pipe. Filled hole with heavy mud to 35', 1/4 sacks hulls and 10 sacks cement. Tied plug.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Trans Era Petroleum, Inc.  
Address Box 633, Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
H. R. Michaelis, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) H. R. Michaelis

(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of April, 19 55

My commission expires 1-30-57

Margie Cooper  
Notary Public.



APR 20 1955

CONSERVATION DIVISION  
Wichita, Kansas

4-20-1955

Trans Era Petroleum, Inc.  
Fatzner #1

SE SE SE 9-26-17  
Edwards County, Kansas

Total Depth: 4940'

15-047-06144-0000

Comm: 3/20/55  
Comp: 4/8/55

Casing

Cement

8 5/8" set @ 357'

265 sacks of Leigh

FORMATION	DEPTH
Sand	155
Shale	220
Shale & Sand Streaks	360
Shale & Shells	370
Shale	440
Sand	490
Shale	585
Red Bed	800
Sand & Red Bed	875
Red Bed & Shale	1140
Anhydrite	1175
Shale & Shells	1450
Shale	1560
Salt	1595
Shale	1805
Shale & Lime	2000
Shale	2175
Lime & Shale	2300
Lime	2405
Lime & Shale	2580
Lime	2685
Lime & Shale	4006
Lime	4485
Shale & Sand	4534
Lime	4545
Lime & Churt	4552
Lime	4608
Lime & Sand	4640
Sand & Shale	4644
Viola	4680
Lime	4835
Sand & Lime	4875
Simpson	4894
Arbuckle	4915
Lime	4940

STATE OF KANSAS )  
                          ) SS:  
RUSSELL COUNTY )

I hereby certify that the above information is true and correct to the best of my knowledge.

*[Handwritten Signature]*

Subscribed and sworn to before me this 19th day of April, 1955

*[Handwritten Signature]*

Notary Public

My commission expires 1-30-57

PLUGGING  
FBI SEC 9 7 26 174  
PAGE 110 LINE 20

RECEIVED  
STATE CORPORATION COMMISSION  
APR 20 1955  
CONSERVATION DIVISION  
Wichita, Kansas