

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 20 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued February 6, 1967.

Operator's Full Name Anadarko Production Company 15-047-00042-0000

Complete Address: P. O. Box 351, Liberal, Kansas

Lease Name Wood Well No. # 1

Location NE NE NE Sec. 26 Twp. 26 Rge. 16 (E) (W) W

County Edwards Total Depth 4785'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Sargent Casing Pulling Service

Address: 121 West 9th St., Liberal, Kansas License No.

Operation Completed: Hour 3:30PM Day 18th Month March Year 1967

The Above well was plugged as follows:

307' of 8 5/8" surface pipe, cemented with 275 sacks. 4618' of 5 1/2" long
string, cemented with 125 sacks. Top perferation 4424'. 20 sacks of cement
was pumped on bottom, bringing the top of the cement to 4315'. 3023' of
5 1/2" long string was recovered from the hole. 5 1/2" casing was pulled up
to 450', and 10 sacks of Gel-Mud was spotted. 5 1/2" casing was pulled up
to 300', and 25 sacks of cement was spotted. Bridge from 40' to 30', and
cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 3/20/67

INV. NO. 4929-W