

KANSAS
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

OCT 15 1959

CONSERVATION DIVISION AGENT'S REPORT

CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-647-80211-0000

File No. 4-18 County: STAFFORD

Location: C-NW-NW Sec. 26 Twp. 26 Rge. 16-(E) (W)

Name of Field: _____ Total Depth: 4500'

I have this date completed supervision of plugging of:

Lease Name: LAMB "B" Well No. 1

Operator's Full Name: L. C. SMITHERMAN

Complete Address: Rx 624 AUGUSTA, KANS

Plugging Contractor: BERT SELF

Address: HUTCHINSON, KANS License No. 48

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 11^{30 AM} Day 9 Month OCT Year 1959

The above well was plugged as follows:

8 1/2" - 302' - 5 1/2" - 4500' - TOP PERF - 4485'
SANDPAPER BOTTOM OF HOLE TO 4475' w/ 5 SP
CMT PLUG THROUGH BAILER - PULLED 3400'
5 1/2" PIPE - FILLED HOLE w/ MUD TO 250'
SET ROCK BRIDGE w/ 20 SP CMT - FILLED
w/ MUD TO 40' - ROCK BRIDGE - w/ 10 SP
CMT CAP TO BASE OF CELLAR.

Signed: Frank Brantford
Conservation Division Agent

Reviewed: J. Lewis Buck
Field Supervisor

Remarks:

INVOICED
DATE 1/12/60
INV. NO. 356-w

LANE "D"

15-647-6021-0000

COMPANY: L. C. Smithman - Oil Producer
CONTRACTOR: L. C. Smithman Drilling Co.

Location: C NW 1/4, Sec. 26-263-16N,
Edwards Co., Kansas
Elevation: 2074

Commenced: Feb. 26, 1959
Completed: April 12, 1959

Casing: 293' 8 5/8" cemented w/3000psi
1199' 5 1/2" cemented w/125 psi.

FIGURES INDICATE POINTS-OF-INTEREST:

0	38	Sand
38	293	Clay, sand, & gravel
293	317	Shale & Shells
317	330	Sand
330	805	Red Bed
805	1070	Red Bed & Shale
1070	1095	Anhydrite
1095	1195	Shale & Shells
1195	1134	Shale & Lime
1134	1538	Shale & Lime
1538	1915	Shale & Shells
1915	2010	Shale & Lime
2010	2156	Lime
2156	2275	Lime
2275	2390	Lime & Shale
2390	2535	Lime & Shale
2535	2615	Lime
2615	2780	Lime & Shale
2780	2915	Lime & Shale
2915	3065	Lime & Shale
3065	3180	Lime & Shale
3180	3310	Lime & Shale
3310	3420	Lime & Shale
3420	3550	Lime & Shale
3550	3600	Lime & Shale
3600	3780	Lime & Shale
3780	3865	Lime & Shale
3865	3955	Lime & Shale
3955	4023	Lime & Shale
4023	4035	Lime & Shale
4035	4109	Lime & Shale
4109	4121	Lime
4121	4198	Lime & Shale
4198	4215	Lime & Shale
4215	4250	Lime
4250	4303	Lime
4303	4333	Lime
4333	4353	Lime
4353	4420	Lime & Shale
4420	4455	Lime & Shale
4455	4480	Mississippi Lime
4480	4500	
4500		TOTAL DEPTH

RECEIVED
STATE CONSERVATION COMMISSION
SEP 23 1959
CONSERVATION DIVISION
Wichita, Kansas

This is to certify the above and foregoing to be a true and correct copy of the Log on the Lane "D" located in the C NW 1/4, Sec. 26-263-16N, Edwards County, Kansas.

L. C. SMITHMAN DRILLING COMPANY

James Cain

Subscribed and sworn to before me this 11th day of June, 1959.

James Cain
(Notary Public)

My Commission expires March 31, 1959.

PLUGGING

File Sec. 26 T. 26 R. 16W

Book Page 4 Line 18