

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-047-20,476-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Oil Properties Co. Inc.

Complete Address Box 335, Andover, Kans 67002

Lease Name Woods Well No. C1

Location C-1/2/NE/4 Sec. 26 Twp. 26 Rge. 16 (East)(West)

County Edwards Total Depth 4580'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase Kansas 67524 License No. 681

Operation Completed: Hour: 3:30 P.M. Day: 10 Month: June Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They ran 4579' of 4 1/2" production pipe with cement out side 4 1/2" at 3894'. Then they plugged back to 4490' + perforated from 4456' to 62'. 1st plug pumped 35 bbls of cement released rubber plug & pumped cement to bottom. Allied Cementing pumping cement. 2nd plug 5 bbls hulls 25 bbls Jell + released rubber plug & pumped 140 bbls of cement on top of rubber plug. They recovered 2735' of 4 1/2" production pipe. The plugging was accomplished by Allied Cementing.

Amount of Surface Casing: 414' of 8 5/8" Cement Circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

JUN 15 1982
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 6-16-82
INV NO. 447-W