

AL
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 13 1967

CONSERVATION DIVISION
Wichita, Kansas

15-047-60069-00-0

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name Johnson Well No. # 1

Location NW NW SE Sec. 24 Twp. 26 Rge. 16 (E) (W) W

County Edwards Total Depth 4546'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: P. O. Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 2:30PM Day 11th Month Jan. Year 1967

The Above well was plugged as follows:

329' of 8 5/8" surface pipe, cement circulated. 4546' of 5 1/2" long string,
no record of cement. Top perferation 4392'. Bottom of the hole was sanded to
4375', and cemented with 5 sacks, through the dump bailer. 3200' of 5 1/2" long
string was recovered from the hole. Bridge plug was pushed in fluid to 325',
bridge plug and rock bridge from 325' to 315'. 1 sack of cement and 1 sack of
Cal-Seal was mixed in a barrel, and put on plug at 315', through the dump
bailer, and let set for 3 hours. Hole was bailed dry, and 24 sacks of cement
was added to the plug. Hole was filled with mud to 40', rock bridge from 40'
to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/13/67

INV. NO. 4597-W

Signed: Audie Elving
Well Plugging Supervisor