

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-047-21007-6000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Stirling Drilling Co.

Complete Address Box 129 Stirling Kansas 67579

Lease Name Mapshaw Well No. A10-40

Location 1876' FNL - 1650' FNL of NW 1/4 Sec. 4 Twp. 26 Rge. 16W (East)(West)

County Edwards Total Depth 4570'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Stirling Drilling Co.

Address Box 129 Stirling Kansas 67579 License No. _____

Operation Completed: Hour: 9:00 AM Day: 9 Month: February Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

The cementite is at 1071'. 1st plug at 1020' with 50 lbs of cement. 2nd plug at 400' on solid bridge with 35 lbs of cement. 3rd plug 40' to 0' on top of rubber plug's solid bridge with 10 lbs of cement. They circulated 10 lbs of cement on rat hole. The cement used was common with 2% gel & 5% CC. All cementing was sparged through drill pipes with hole full of foamy mud. The plugging was accomplished by allied cementing, then they pulled pumpout of water with plug with 50 lb cement.

Amount of Surface Casing: 423' of 8 3/8" cement circulation

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul Luth
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

FEB 17 1982

Signed: _____
Conservation Division Agent

INVOICE CONSERVATION DIVISION
Wichita, Kansas

DATE 2-19-82

INV. NO. 9457-W