

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -047- 00293-00-61 (of this well)

Operator's Full Name Southland Royalty, Trust Estate of H.A. Chapman.

Complete Address 404 Cities Ser., Bldg., Tulsa, Ok. 74119

Lease Name Bordewick Well No. 1

Location C SW SE Sec. 23 Twp. 26s Rge. 18 (E) (W) W

County Edwards Total Depth 3351

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated Drilled to 3351' From 3306'. Permit was 3306

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Ks. 67524 License No. 683

Operation Completed: Hour 5:15 Pm. Day 5 Month 2 Year 1980

The above well was plugged as follows:

359' 8 5/8" casing w/250 sax cement. 4 1/2" casing set at 3351' w/150
sax cement. Plug back to 3321'-Top perforated at 3311'-Push plug to
3200'-Sand back to 3175'- Top sand w/4 sax mixed cement w/dump bailer
Pull 2755' casing. Sun mixed & pumped 8 sax hulls-25 sax gel-125 sax
50/50 posmix cement w/4% gel & 3% cc to top of casing. Shut in w/300#
pressure.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2-7-80

INV. NO. 1487-w

Signed: [Signature]
Well Plugging Supervisor
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1980